



- NOTES:
1. SELECT BACKFILL SHALL BE COMPACTED IN 6" LIFTS.
  2. IF PREFERRED MATERIAL IS NOT AVAILABLE ON SITE, IT IS TO BE BROUGHT IN.
  3. WHEN SELECT BACKFILL NOT AVAILABLE - 6" OF #68 STONE REQ'D ABOVE PIPE.
  4. BELL HOLES WHERE APPLICABLE SHALL BE PROVIDED FOR EACH JOINT TO ALLOW JOINT ASSEMBLY AND TO ENSURE THAT THE PIPE BARREL WILL BE FLAT ON TRENCH BOTTOM.
  5. THIS DETAIL APPLICABLE FOR DEPTHS LESS THAN 14 FEET. SEE PLANS FOR MODIFICATIONS IN DEEPER TRENCHES.
  6. WHEN PIPE PLACED ON STABLE SOIL, SCRAPE THE BOTTOM OF THE TRENCH, REMOVE ALL STONES TO ENSURE THE PIPE DOES NOT REST ON ROCK, THEN COMPACT THE SOIL.

<b>AUGUSTA COUNTY SERVICE AUTHORITY VERONA, VIRGINIA</b>	
<b>SCALE: NTS</b>	<b>DRAWN BY: ACSA</b>
<b>DATE: FEB. 1996</b>	<b>REVISED: OCT. 2020</b>
<b>TYPICAL DUCTILE IRON PIPE INSTALLATION AND BEDDING REQUIREMENTS</b>	
<b>DRAWING NUMBER: W-1</b>	<b>PAGE: 1 OF 1</b>